

No.	Item Description	Unit	Quantity	Rate	Amount	
					£	
	<u>Sub-Total Page Nine C/F</u>					
3.22	Supply and paint 150m wide strip around perimeter of pit using floor paint in 50mm diagonal alternating red and yellow.		Item			
3.23	Supply and install headlight tester as per Specification.		Item			
3.24	Supply and install 6No mobile column lifts as per Specification.		Item			
3.25	Supply and install four post lift as per Specification.		Item			
3.26	Saw, cut ex-tarmac 10m x 4m Excavate 200mm deep and remove off site to NIEA registered site.	m	18			
3.27	Supply and place 200mm deep 40N concrete base to storage shed with 1 No layer of A393 mesh.	m ²	40			
3.28	Supply and install covered storage area as per Specification and Drawing No 14/1604-10.		Item			
3.29	Supply and install diesel emissions tester as per Specification.		Item			
4.0	<u>CONTINGENCIES</u> Include the provisional sum of £20,000 for undefined work.				£20,000	00
	TOTAL				£	